



## Campbell Job - Material List

Qty					Total
Code	Phase	Item	UOM	Use	Total
13.11.12	Pilings	<b>#2 PT - 2" x 10" x 16'</b>			8
		ea		Piling Bracing - 10'+ Ground Floor	8
		<b>#2 PT - 2" x 12" x 16'</b>			50
		ea		Piling Girders	50
		<b>#2 PT - 8" x 8" x 24'</b>			50
		ea		Piling - 16' Ground Floor	50
		<b>Galv. Carriage Bolt - 3/4" x 12"</b>			32
		ea		Piling Bracing Bolt (2 each end)	32
		<b>Galv. Hex Bolt - 3/4" x 10"</b>			100
		ea		Girder Strap Bolt	100
		<b>Galv. Hex Nut - 3/4"</b>			132
		ea		Girder Strap Nut	100
				Piling Bracing Nut (2 each end)	32
		<b>Galv. Washer - 3/4"</b>			132
ea		Girder Strap Washer	100		
		Piling Bracing Washer (2 each end)	32		
<b>Simpson PS418</b>			100		
ea		Piling Strap - 7 ga. x 4" x 18"	100		
14.10.10	Ground Floor Wall Framing	<b>#2 PT - 2" x 6" x 16'</b>			2
		ea		Bottom Plate	2
		<b>#2 SPF - 2" x 4" x 16'</b>			4
		ea		Deadwood	1
				Purlin	3
		<b>#2 SPF - 2" x 6" x 10' Pre-Cut</b>			20
		ea		Stud	20
<b>#2 SPF - 2" x 6" x 16'</b>			3		
ea		Double Top Plate	3		
<b>Sill Sealer - 6" x 50'</b>			1		
ea		Sill Sealer	1		
14.10.12	1st Floor Framing	<b>#2 PT - 2" x 2" x 8'</b>			11

Code	Phase	Item	UOM	Use	Total
14.10.12	1st Floor Framing	#2 PT	ea	Ledger Strip	11
		#2 PT - 2" x 12" x 8'			11
		ea		Deck Joist	11
		#2 PT - 2" x 12" x 10'			10
		ea		Deck Joist	10
		#2 PT - 2" x 12" x 12'			29
		ea		Deck Joist	13
				Deck Joist - Cut to 6'	16
		#2 PT - 2" x 12" x 16'			11
		ea		Ledger/Rim Board (1 each end)	11
		#2 SYP - 2" x 10" x 16'			6
		ea		Truss Rim Board (1 each end)	6
		#2 SYP - 2" x 12" x 20'			4
		ea		Stair Stringer	4
		Floor Truss - 12"			788
		lf		Floor Truss	788
		Galv. Carriage Bolt - 5/8" x 8"			94
		ea		Ledger Board Bolt	94
		Galv. Flashing - 14" x 50'			2
		roll		Ledger Flashing	2
		Galv. Hex Nut - 5/8"			94
		ea		Ledger Board Nut	94
		Galv. Washer - 5/8"			94
		ea		Ledger Board Washer	94
14.10.13	1st Floor Sheathing	Advantech - 3/4" x 4' x 8', T&G			50
		ea		Floor Sheathing	50
		PT CDX - 3/4" x 4' x 8'			22
		ea		Deck Sheathing	22
		Subfloor Glue - 29 oz.			13
		ea		Floor Glue	13
14.10.14	1st Floor Wall Framing	#2 SPF - 2" x 4" x 10' Pre-Cut			381
		ea		Stud	335
					46
		#2 SPF - 2" x 4" x 16'			188
		ea		Bottom Plate	22
				Deadwood	12

Code	Phase	Item	UOM	Use	Total
14.10.14	1st Floor Wall Framing	#2 SPF	ea	Double Top Plate	44
				Purlin	29
				Sill Plate	12
				Wall Bracing	69
		#2 SPF - 2" x 6" x 16'			5
		ea		Bottom Plate	2
				Double Top Plate	3
		#2 SPF - 2" x 6" x 24'			20
		ea		Stud	20
		#2 SYP - 2" x 10" x 8'			13
		ea		Header	2
				Header - Cut to 4' or less	11
		Pocket Door Kit - 8/0			2
		ea		Pocket Door Kit	2
Simpson CS16			1		
roll		Coil Strapping	1		
14.10.15	2nd Floor Framing	#2 PT - 2" x 2" x 8'			6
		ea		Ledger Strip	6
		#2 PT - 2" x 12" x 8'			11
		ea		Deck Joist	11
		#2 PT - 2" x 12" x 10'			10
		ea		Deck Joist	10
		#2 PT - 2" x 12" x 12'			13
		ea		Deck Joist	13
		#2 PT - 2" x 12" x 16'			6
		ea		Ledger/Rim Board (1 each end)	6
		#2 SYP - 2" x 10" x 16'			6
		ea		Truss Rim Board (1 each end)	6
		#2 SYP - 2" x 12" x 22'			4
		ea		Stair Stringer	4
Floor Truss - 12"			787		
lf		Floor Truss	787		
Galv. Carriage Bolt - 5/8" x 8"			48		
ea		Ledger Board Bolt	48		
Galv. Flashing - 14" x 50'			1		
roll		Ledger Flashing	1		

Code	Phase	Item	UOM	Use	Total
14.10.15	2nd Floor Framing	<b>Galv. Hex Nut - 5/8"</b>			48
		ea		Ledger Board Nut	48
		<b>Galv. Washer - 5/8"</b>			48
		ea		Ledger Board Washer	48
14.10.16	2nd Floor Sheathing	<b>Advantech - 3/4" x 4' x 8', T&amp;G</b>			50
		ea		Floor Sheathing	50
		<b>CDX Treated - 3/4" x 4' x 8', T&amp;G</b>			14
		ea		Deck Sheathing	14
		<b>Subfloor Glue - 29 oz.</b>			13
		ea		Floor Glue	13
14.10.17	2nd Floor Wall Framing	<b>#1 PT - 4" x 4" x 8'</b>			3
		ea		Porch Post - Cut to 4'	3
		<b>#2 SPF - 2" x 4" x 9' Pre-Cut</b>			497
		ea		Stud	425
					72
		<b>#2 SPF - 2" x 4" x 16'</b>			190
		ea		Bottom Plate	28
				Deadwood	14
				Double Top Plate	56
				Purlin	22
				Sill Plate	19
				Wall Bracing	51
				<b>#2 SYP - 2" x 10" x 8'</b>	
ea		Header - Cut to 4' or less	18		
14.10.21	Ceiling Framing	<b>#2 SYP - 2" x 12" x 16'</b>			10
		ea		Ceiling Beam	10
		<b>Advantech - 3/4" x 4' x 8', T&amp;G</b>			5
		ea		Floor Sheathing - Attic	5
		<b>Subfloor Glue - 29 oz.</b>			2
ea		Floor Glue	2		
14.10.22	Wall Sheathing	<b>Button-Cap Nails - 1" (3,000/Box)</b>			3
		box		Housewrap Nails	3
		<b>OSB - 7/16" x 4' x 8'</b>			116
		ea		Wall Sheathing	116
		<b>PT CDX - 1/2" x 4' x 8'</b>			18
ea		Wall Sheathing	18		
		<b>Tyvek - 9' x 150'</b>			4

Code	Phase	Item	UOM	Use	Total
14.10.22	Wall Sheathing	Tyvek	roll	Housewrap	4
		Tyvek Tape - 2" x 165'			7
		roll		Housewrap Tape	7
14.10.23	Roof Framing	#2 SPF - 2" x 4" x 16'			46
		ea		Soffit Blocking	17
					29
		#2 SPF - 2" x 6" x 16'			24
		ea		Subfascia	9
					15
		Roof Trusses			2047
		sf		Roof Trusses	2047
14.10.24	Roof Sheathing	Button-Cap Nails - 1" (3,000/Box)			2
		box		Roof Felt Nails	2
		Roof Felt - 30#, 2 SQ			13
		roll		Roof Felt	13
		TechShield - 7/16" x 4' x 8'			84
		ea		Roof Sheathing	84
14.10.26	Framing Nails	Gun Nails - 2-3/8" Galv. Ring Shank (5,000/box)			12
		box		Sheathing Nails	12
		Gun Nails - 3" Galv. Ring Shank (4,000/box)			4
		box		Wall Framing Nails	4
		Gun Nails - 3-1/4" Galv. Smooth (4,000/box)			12
		box		Floor/Ceiling/Roof Framing Nails	12
14.11.11	Roof Flashing	Drip Edge - Galv.			339
		lf		Drip Edge	215
					124
		Hydro-Stop Waterproofing			647
		sf		Hydro-Stop	647
14.15.11	Boxing	#2 SPF - 2" x 4" x 16'			38
		ea		Porch Beam Blocking	38
		HardieSoffit - 1/4" x 12" x 12', Solid			11
		ea		Rake Soffit - 12"	11
		HardieSoffit - 1/4" x 12" x 12', Vented			19
		ea		Soffit - 12"	19
		MiraTEC - 1" x 8" x 16'			34
		ea		Fascia	15

Code	Phase	Item	UOM	Use	Total		
14.15.11	Boxing	MiraTEC	ea	Porch Beam Bottom	10		
				Rake Fascia	9		
		MiraTEC - 1" x 12" x 16'			19		
		ea	Porch Beam Sides	19			
		MiraTEC - 5/4" x 6" x 16'			24		
		ea	Frieze	15			
			Rake Frieze	9			
		PVC Crown - 4-1/4"			355		
		lf	Frieze Mold	225			
			Rake Frieze Mold	130			
		PVC Shingle Mold - 1-5/8"			130		
		lf	Shingle Mold	130			
		14.15.12	Exterior Trim	#1 RPT - 2" x 4"			128
				lf	Window/Door Trim	128	
MiraTEC - 5/4" x 4" x 16'					48		
ea	Inside Corner			7			
	Window/Door Trim			41			
MiraTEC - 5/4" x 6" x 16'					41		
ea	Outside Corner			31			
	Window/Door Trim	10					
Z Flashing - Galvalume			148				
lf	Window/Door Flashing	148					
14.15.13	Siding	HardiePanel - 5/16" x 4' x 8'			50		
		ea	Ground Floor Ceiling	50			
		HardiePlank - 5/16" x 8-1/4" x 12'			554		
		ea	Lap Siding	554			
		PlyBead - 3/8" x 4' x 8'			25		
		ea	Porch Ceiling	25			
PVC Crown - 4-1/4"			251				
lf	Porch Ceiling Crown	251					
16.12.11	Drywall Material	Drywall - 1/2" x 48" x 12'			119		
		bd	Wall Drywall	119			
		Drywall - 1/2" x 54" x 12'			119		
		bd	Wall Drywall	119			
		Drywall - 5/8" x 48" x 12'			63		
bd	Ceiling Drywall	63					

Code	Phase	Item	UOM	Use	Total
17.10.10	Decks	#1 RPT - 5/4" x 6" x 16'			137
			ea	Decking	54
					83
17.10.11	Columns & Rails	#1 RPT - 2" x 2" x 12'			194
			ea	Picket	194
		#1 RPT - 2" x 4"			388
			lf	Bottom Rail	194
				Top Rail	194
		#1 RPT - 2" x 6"			194
			lf	Rail Cap	194
		FG Column/Cap/Base - 8" Round x 10'			14
			ea	Porch Column	14